Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Debris Removal								
	Kamaman Temple								
	Inside Fencing		1	10.50	1.20	0.20	2.52		
	Vivekananda Park		1	21.00	2.30	0.25	12.08		
	For Fencing								
	Western Side								
	For Volley Ball Court		12	0.75	0.65	0.70	4.10		
	Western Side								
	Northern Side		11	0.75	0.65	0.90	4.83		
	Eastern Side		8	0.75	0.65	0.90	3.51		
	Southern Side		10	0.75	0.65	0.90	4.39		
	Northern Side		12	0.75	0.65	0.90	5.27		
	Benches Platform		1	126.00	0.75	0.75	70.88		
			24	2.10	1.60	0.25	20.16		
	For Pathway		3	3.00	2.70	0.25	6.08		
	Deo Marvel Park								
	Southern Side								
			1	29.80	2.15	0.25	16.02		
	Western Side								
			1	51.00	2.20	0.25	28.05		
	Northern Side								
			1	44.30	2.30	0.25	25.47		
	Eastern Side								
			1	34.40	2.30	0.25	19.78		
	Gate Entrance								
			1	6.20	5.80	0.25	8.99		
	Southern Side								
			1	2.20	2.10	0.25	1.16		
	Benches Platform								
	Deo Marvel Layout								
	Norhern Side								
	Platform A to E		5	2.10	1.20	0.25	3.15		
	Western Side								
	Platform F		1	3.75	3.70	0.25	3.47		
	Platform G To J		4	2.10	1.50	0.25	3.15		
	Gym platform								
			1	17.00	5.70	0.25	24.23		
	Vivekananda Park								
	Gym Platform-1		1	5.00	2.60	0.25	3.25		
	Gym Platform-2		1	15.50	4.60	0.25	17.83		
	Gazib platform Area								
	Area of hexagon=(S Squareroot S2)/2		(3*1.73*3.3*3.3)/2			0.25	7.06		
	Benches Platform								
			7	2.10	1.50	0.25	5.51		
			3	2.10	1.20	0.25	1.89		

1125.28

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Shankar Nag Park								
			1	13.50	10.00	0.25	33.75		
	For Kerb Stone								
			1	2.10	0.20	0.25	0.36		
	Shoulder Drain								
			2	1.10	0.20	0.25	0.11		
	For Steps		4	0.45	0.20	0.25	0.09		
	Pole Surrounding		4	0.45	0.20	0.25	0.09		
	Surrounding		4	0.45	0.20	0.25	0.09		
	debris		2	5.00	2.50	0.25	6.25		
	Benches Platform								
	Vivekananda Park								
			10	2.10	0.20	0.25	1.05		
			10	1.50	0.20	0.25	0.75		
	Norhern Side								
	Platform A To E		5	2.20	0.20	0.25	0.55		
			10	1.40	0.20	0.25	0.70		
	Western Side								
	Platform F		2	3.80	0.20	0.25	0.38		
	Platform G To J		8	1.80	0.20	0.25	0.72		
	Platform F To J		1	21.40	0.20	0.25	1.07		
	Gym Platform								
			1	17.00	0.20	0.25	0.85		
			1	5.90	0.20	0.25	0.30		
							1179.19	**480.70**	**566835.87**
	Approved Amount			**480.70**					
94	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. complete as per specifications and directions of the Engineer in charge.								
		Cum							
	Hanuman Temple Yelahanka								
	North Side LHS Gate		1	13.90	0.90	0.15	1.88		
	North Side RHS Gate		1	19.70	0.90	0.15	2.66		
	Eastern Side		1	83.50	0.90	0.15	11.27		
	Southern Side		1	38.00	0.90	0.15	5.13		
	Western Side		1	88.00	0.90	0.15	11.88		
	wall for tree		1	5.60	0.90	0.15	0.76		
	Park Inside Temple								
	Northen Side		4	0.30	0.30	0.15	0.05		
	Southern Side		4	0.30	0.30	0.15	0.05		
	Eastern Side		10	0.30	0.30	0.15	0.14		
	Western Side		10	0.30	0.30	0.15	0.14		
	Hanuman Temple Yelahanka								
	For Benches		1	2.00	1.40	0.15	0.42		
	RHS of Temple		1	1.90	1.30	0.15	0.37		
	Infront of Statue		1	3.40	1.40	0.15	0.71		
	LHS of Temple		1	7.50	1.10	0.15	1.24		

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Shankar Nag Park						26.69		
	Western Side								
	Southern Side		1	80.00	1.20	0.15	14.40		
	Northen Side		1	104.00	1.20	0.15	18.72		
	Eastern Side		1	74.00	1.20	0.15	13.32		
	Vivekananda Park		1	84.00	1.20	0.15	15.12		
	New Drain								
	Beside Entrance Building								
			1	15.40	1.30	0.15	3.00		
	At Entrance gate								
			1	15.10	1.30	0.15	2.94		
	For Sump		1	4.60	3.40	0.15	2.35		
	Pathway								
	Vivekananda Park								
	Eastern Side								
			1	108.00	2.50	0.15	40.50		
	Southern Side								
			1	134.30	2.50	0.15	50.36		
	At Southern Side Gate								
			1	4.80	2.00	0.15	1.44		
	Western Side								
			1	130.00	2.50	0.15	48.75		
	Northern Side								
			1	129.00	2.50	0.15	48.38		
	At Park Centre Path Way								
			1	120.00	2.50	0.15	45.00		
	At Entrance To Cricket Practice Ground								
			1	3.20	2.50	0.15	1.20		
	At Entrance ToYoga Stage								
			1	49.00	3.00	0.15	22.05		
	At Gazebo								
			1	47.00	2.00	0.15	14.10		
	Around Children Play Area								
			1	53.50	2.00	0.15	16.05		
	At Entrance To Volley Ball Court								
			1	30.00	3.40	0.15	15.30		
	Benches Platform								
			24	2.10	1.60	0.15	12.10		
			3	3.00	2.70	0.15	3.65		
	Ramp Concrete								
	Nisargha Park								
	At Northern Side gate								
			1	9.45	1.55	0.15	2.20		
	At Wester Side Gate								
			1	7.30	1.70	0.15	1.86		
							429.48		

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Middle of Ground								
			2	3.70	2.00	0.15	2.22		
	Deo Marvel Park								
	At Southern Side gate								
			1	6.20	7.00	0.15	6.51		
	For Kerb Stone								
	Vivekananda Park								
	Eastern Side								
			1	218.00	0.20	0.10	4.36		
	Southern Side LHS								
			1	271.50	0.20	0.10	5.43		
	At Southern Side Gate								
			1	16.00	0.20	0.10	0.32		
	Western Side LHS								
			1	264.00	0.20	0.10	5.28		
	Northern Side								
			1	261.50	0.20	0.10	5.23		
	At Park Centre Path Way								
			1	240.00	0.20	0.10	4.80		
	At Gazebo								
			1	60.00	0.20	0.10	1.20		
	Around Children Play Area								
			1	58.00	0.20	0.10	1.16		
	At Entrance To Volley Ball Court								
			1	69.00	0.20	0.10	1.38		
	At Entrance To Pathway								
			1	76.60	0.20	0.10	1.53		
	At Gym Eqipuments-1								
			1	38.00	0.20	0.10	0.76		
	At Gym Eqipuments-2								
			1	19.00	0.20	0.10	0.38		
	At Main Gate Entrance								
	Tree Guards Surrounding								
			1	33.00	0.20	0.10	0.66		
	Benches Surrounding								
			1	205.00	0.20	0.10	4.10		
	B\w Volley Ball Court To Basket Ball Court								
			1	108.00	0.20	0.10	2.16		
	At main Gate Connecting To Drain								
			2	18.00	0.20	0.10	0.72		
	At Park Surrounding								
			1	20.00	0.20	0.10	0.40		
	At Watch Man Room Surrounding						478.08		

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
			1	24.50	0.20	0.10	0.49		
	At Main Entrance To Yoga Stage								
			1	105.00	0.20	0.10	2.10		
	At Drain Surrounding								
			1	61.00	0.20	0.10	1.22		
	Deo Marvel Park								
	Eastern Side								
			1	83.00	0.20	0.10	1.66		
	Northern Side								
			1	92.00	0.20	0.10	1.84		
	Western Side								
			2	49.00	0.20	0.10	1.96		
	Deduct		-1	5.00	0.20	0.10	-0.10		
	Southern Side LHS								
			1	65.00	0.20	0.10	1.30		
	Gym Surrounding								
			1	17.30	0.20	0.10	0.35		
			2	6.20	0.20	0.10	0.25		
	Toilet								
	Vivekananda Park								
	Footing		8	2.00	2.00	0.15	4.80		
	Foundation		2	5.50	1.00	0.15	1.65		
			2	5.50	1.00	0.15	1.65		
	Floor Area		1	5.50	5.50	0.15	4.54		
	Vivekananda Park								
			2	5.50	3.00	0.20	6.60		
			2	5.50	3.00	0.20	6.60		
							514.98	**5560.70**	**2863639.79**
	Approved Amount			**5560.70**					
95	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications. complete as per specifications and directions of the Engineer in charge.								
		Cum							
							0.00	**129.54**	**0.00**
	Approved Amount			**129.54**					
96	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:8, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. complete as per specifications and directions of the Engineer in charge.								
		Cum							
	Hanuman Temple Yelahanka								
	North Side LHS Gate		1	14.00	0.60	0.60	5.04		
	North Side RHS Gate		1	20.00	0.60	0.60	7.20		
	Eastern Side		1	84.00	0.60	0.60	30.24		
	Southern Side		1	38.00	0.60	0.60	13.68		

56.16

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Western Side								
	Shankar Nag Park		1	93.50	0.60	0.60	33.66		
	Western Side								
	Southern Side		1	80.00	0.60	0.60	28.80		
	Northen Side		1	104.00	0.60	0.60	37.44		
	Eastern Side		1	74.00	0.60	0.60	26.64		
			1	84.00	0.60	0.60	30.24		
	Approved Amount			**4811.28**			**212.94**	**4811.28**	**1024513.20**
97	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.complete as per specifications and directions of the Engineer in charge.								
	Hanuman Temple Yelahanka	**Cum**							
	North Side LHS Gate								
	North Side RHS Gate		1	14.00	0.45	0.60	3.78		
	Eastern Side		1	20.00	0.45	0.60	5.40		
	Southern Side		1	84.00	0.45	0.65	24.57		
	Western Side		1	38.00	0.45	0.60	10.26		
	Shankar Nag Park		1	93.50	0.45	0.60	25.25		
	Western Side								
	Southern Side		1	80.00	0.45	0.40	14.40		
	Northen Side		1	104.00	0.45	0.40	18.72		
	Eastern Side		1	74.00	0.45	0.40	13.32		
			1	84.00	0.45	0.40	15.12		
	Approved Amount			**5870.10**			**130.82**	**5870.10**	**767897.11**
98	Providing ruled pointing to coursed stone masonry with cement mortar, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. – do – cement mortar 1:3. complete as per specifications and directions of the Engineer in charge.								
	Hanuman Temple Yelahanka	**Sqm**							
	North Side LHS Gate								
	North Side RHS Gate		1	14.00		0.60	8.40		
	Eastern Side		1	20.00		0.60	12.00		
	Southern Side		1	84.00		0.65	54.60		
	Western Side		1	38.00		0.60	22.80		
	Shankar Nag Park		1	93.50		0.60	56.10		
	Western Side								
	Southern Side		1	80.00		0.40	32.00		
	Northen Side		1	104.00		0.40	41.60		
	Eastern Side		1	74.00		0.40	29.60		
			1	84.00		0.40	33.60		
	Approved Amount			**104.92**			**290.70**	**104.92**	**30,499.90**

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
99	Providing and constructing load bearing wall with solid concrete blocks of size 400x200x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 5.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. complete as per specifications and directions of the Engineer								
	Toilet Area Nishargha Park	Sqm							
	Longer Wall								
	Shorter Wall		3	3.30		2.70	26.73		
	Parafit Wall		4	1.65		2.70	17.82		
			2	4.20		0.30	2.52		
	Deduction		2	4.70		0.30	2.82		
			-2	0.75		1.85	-2.78		
			-2	0.90		0.45	-0.81		
	Hanuman Temple								
	North Side LHS Gate		1	13.90		1.25	17.38		
	North Side RHS Gate		1	19.70		1.25	24.63		
	Eastern Side								
			1	83.50		1.40	116.90		
	Southern Side								
			1	38.10		1.35	51.44		
	Western Side								
			1	88.20		1.40	123.48		
	Wall For Tree		1	5.00		1.50	7.50		
	For Columns								
	West		-6	0.20		1.35	-1.62		
	North		-21	0.20		1.35	-5.67		
	East		-6	0.20		1.40	-1.68		
	South		-18	0.20		1.40	-5.04		
	Deo Marvel Park								
	Compound Wall								
	North Side		1	52.00		1.50	78.00		
	Toilet								
	Vivekananda Park								
	Wall								
			3	5.50		3.00	49.50		
			2	5.50		3.00	33.00		
	Parapet Wall		2	5.50		0.90	9.90		
			2	5.50		0.90	9.90		
	Deduction								
	Door D		-2	0.90		2.10	-3.78		
	Door D1		-4	0.75		2.10	-6.30		
	Ventilator V		-2	3.15		0.50	-3.15		
	Ventilator V1		-2	0.60		0.50	-0.60		
	Ramp								
	Vivekananda Park								
			2	5.50		0.40	4.40		

Rs 44.42

Scanned by TapScanner

CF 5141.48

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
			2	5.50		0.40	4.40		
	Approved Amount				976.39		548.88	976.39	535914.52
100	Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. complete as per specifications and directions of the Engineer in charge.								
		Sqm							
	Nisarga Park								
	For Grill Work								
	Southern Side								
			3	48.60	0.60		87.48		
	Western Side								
			3	70.50	0.60		126.90		
	Northern Side								
			3	41.79	0.60		75.22		
	Deo Marvel Park								
	For Grill Work								
	Eastern Side								
			1	52.30	0.55		28.77		
	Northern Side								
			1	51.00	0.55		28.05		
	Western Side								
			1	42.90	0.55		23.60		
	Southern Side								
			1	46.70	0.60		28.02		
	Hanuman Temple								
	North Side LHS Gate		2	13.90		1.25	34.75		
	North Side RHS Gate		3	19.70		1.25	73.88		
	Eastern Side								
			2	83.50		1.40	233.80		
	Southern Side								
			2	38.10		1.35	102.87		
	Western Side								
			2	88.20		1.40	246.96		
	Wall For Tree		2	5.00		1.50	15.00		
	For Columns								
	West		6	0.20		1.35	1.62		
	North		21	0.20		1.35	5.67		
	East		6	0.20		1.40	1.68		
	South		18	0.20		1.40	5.04		
	Vivekananda Park								
	Northern Side								
			3	137.00	0.60		246.60		
	Deo Marvel Park								
	Compound Wall								
	North Side		1	48.00		1.50	72.00		
	Toilet								
	External Plastering								

1437.90

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Vivekananda Park								
	Wall								
			2	5.50		2.90	31.90		
			2	5.50		2.90	31.90		
	Parapet Wall		4	5.50		0.90	19.80		
			4	5.50		0.90	19.80		
	Deduction								
	Door D		-2	0.90		2.10	-3.78		
	Ventilator V		-2	3.15		0.50	-3.15		
	Ventilator V1		-2	0.60		0.50	-0.60		
	Window		-2	1.20		1.00	-2.40		
							1531.37	**262.30**	**401672.97**
	Approved Amount			**262.30**					
101	Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. complete as per specifications and directions of the Engineer in charge.								
		Sqm							
	Hanuman Temple								
	North Side LHS Gate		2	13.90		1.45	40.31		
	North Side RHS Gate		3	19.70		1.47	86.88		
	Eastern Side								
			2	83.50		1.50	250.50		
	Southern Side								
			2	38.10		1.50	114.30		
	Western Side								
			2	88.20		1.50	264.60		
	Wall For Tree		2	5.00		1.50	15.00		
	For Columns								
			51	0.20		1.45	14.79		
							786.38	**109.20**	**85,873.31**
	Approved Amount			**109.20**					
102	Removing and resetting of kerb stones.complete as per specifications and directions of the Engineer in charge.								
		Mtr							
	Hanuman Temple Yelahanka								
	South East		1	140.00			140.00		
	North		1	140.00			140.00		
	For Benches		1	7.00			7.00		
	RHS of Temple		1	15.00			15.00		
	Infront of Statue		1	20.00			20.00		
	LHS of Temple		1	19.00			19.00		
	Shankarnag Park								
	South RHS		1	99.00			99.00		
	LHS		1	80.00			80.00		
	West RHS		1	42.00			42.00		
	LHS		1	18.50			18.50		
	At gate		1	11.00			11.00		
							591.50		

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	RHS								
	LHS		1	30.00			30.00		
	North RHS		1	32.00			32.00		
	LHS		1	69.00			69.00		
	East RHS		1	69.50			69.50		
	LHS		1	73.00			73.00		
	At Gazebo		1	66.00			66.00		
	LHS		1	28.00			28.00		
	East Walk track		1	28.00			28.00		
	LHS		2	30.00			60.00		
			2	3.00			6.00		
	Approved Amount						**1053.00**	**105.99**	**111606.84**
				105.99					
103	Providing and fixing pre cast solid concrete kerb stones of size 450x150x500 mm made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting ete., complete as per specifications and directions of the Engineer in charge.								
		Nos							
	New Kerbs								
	Infront of Hanuman Statue								
			2	27.00			54.00		
	Chikkabommasandra arch for Benches		2	5.00			10.00		
	Suronding nagara Katte								
	North		1	5.20			5.20		
	East		1	2.40			2.40		
	East		1	1.45			1.45		
	South		1	5.10			5.10		
	West		1	9.30			9.30		
	South		1	8.00			8.00		
	East		1	15.30			15.30		
	Shankarnag Park								
	New Kerbs South At gate		1	6.00			6.00		
	South Walk track RHS		1	16.00			16.00		
	West Walk track RHS		2	16.00			32.00		
	LHS		1	10.00			10.00		
	At gate		1	7.00			7.00		
	North Walk track		2	18.00			36.00		
							217.75		
							484.00	**472.13**	**228513.15**
	Approved Amount			**472.13**					
104	Removing and resetting of available heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of block of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specification. (for available cobble stones) complete as per specifications								
		Sqm							
	Hanuman Temple Yelahanka								

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	South East								
	West		1	52.00	2.00		104.00		
	East		1	22.00	1.75		38.50		
	Step		1	31.50	1.85		58.28		
	Shankarnag Park		1	25.60	2.00		51.20		
	Around gazebo								
	South		1	15.10	1.85		27.94		
	West		1	97.00	3.10		300.70		
	North		1	78.00	3.10		241.80		
	East		1	69.50	3.10		215.45		
	South Walk Track		1	73.00	3.10		226.30		
	West Walk Track		1	29.00	3.10		89.90		
	North Walk Track		1	84.30	3.10		261.33		
	East walk Tarck		1	28.30	3.10		87.73		
			1	32.00	3.10		99.20		
							1802.32	**581.69**	**1048390.26**
	Approved Amount			**581.69**					
105	Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick for flooring conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification. complete as per specifications and directions of the Engineer in charge.								
		Sqm							
	Hanuman Temple Yelahanka								
			12	2.05	1.40		34.44		
	Vivekananda Park								
			24	2.10	1.60		80.64		
			3	3.00	2.70		24.30		
	For Gazeboo								
			1	42.00	1.00		42.00		
	Shankar Nag Park		1	13.50	10.00		135.00		
	Deo Marvel Layout								
	Norhern Side		5	2.10	1.20		12.60		
	Western Side		1	3.75	3.70		13.88		
			19	2.10	1.50		59.85		
	Gym platform		1	17.00	5.70		96.90		
	Vivekananda Park								
	Gym Platform-1		1	5.00	2.60		13.00		
	Gym Platform-2		1	15.50	4.60		71.30		
	Gazib platform Area								
	Area of hexagon=(S Squareroot S2)/2			(3*1.73*3.3*3.3)/2			28.26		
	Benches Platform								
			7	2.10	1.50		22.05		
			3	2.10	1.20		7.56		
							641.77	**1318.98**	**846487.28**
	Approved Amount			**1318.98**					

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
106	Sand filling in wells complete as per drawing and technical specifications including cost of all materials, labour, HOM, form works, scaffolding & centering complete as per specifications. complete as per specifications and directions of the Engineer in charge.								
		Sqm							
									0.00
	Approved Amount			2834.95			0.00	2834.95	
107	Supplying and fixing polished grey granite slab benches of size 5 feet width of seating slab with bottom slab of 75mm th. with 1.5 feet width with two stands strong base with back slab (suport) machine cutting top slab mirror polish with 50 mm Th. with 1.5 feet depth side slab of 100 mm th. 2.5 feet height. including bull nosing of all edges, fixing in CC 1:2:4 including loading & unloading and with all lead and lift etc., complete and executing the work as per								
		Nos							
			8				8.00		
							8.00	18382.00	147056.00
	Approved Amount			18382.00					
108	Fabricating, providing and erecting in position of MS Hot Dip Galvanised Sq. Hallow Poles of 132 X 132 Heavy gauge of length 3000mm with MS. Hot dip Galvanised grill work as per approved design and drawing of chief architect. Using 12 X 75mm galvanised flat for alround frame and 20 X 20mm galvanised forged design with square for vertical at 150mm c/c as shown in the drawing including providing forged ornamental arrowhead at top and bottom. The work is inclusive of throughing flat, square rods, placing welding all the joints, including grinding, finishing 2 coats of anticorrosive paint over one coat of metal primer. The rate is inclusive of all materials like MS. Hollow galvanized pipe, flats, forged square rods, cost of labour for all items of work cost painting, welding, cutting, grinding with all lead and lift as per specification including loading and unloading with cost and conveyance of all materials, labour, machinery andincidental charges for the successful completion of the work as per the direction of the Engineer-in-charge of the work. (Data Rate)								
		Rmt							
	For Grill Work								
	Shankarnag Park Yelahanka								
	west side		1	78.20		2.15	168.13		
	North Side		1	74.00		2.15	159.10		
	East		1	82.80		2.15	178.02		
	South		1	102.90		2.15	221.24		
	Nisarga Park								
	Southern Side		1	48.60		2.40	116.64		
	Western Side		1	70.50		2.40	169.20		
	Northern Side		1	41.80		2.40	100.32		
	Deo Marvel Park								
	Southern Side		1	45.90		2.50	114.75		
	Western Side		1	42.60		2.50	106.50		
	Northern Side		1	60.90		2.50	152.25		
	Eastern Side		1	47.90		2.50	119.75		
							1605.90		
					Upto 125%		865.00	9235.44	7988655.60

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
					Above 125%		740.90	9235.44	6842491.32
	Approved Amount			9235.44					
109	Fabricating, providing and erecting in position Hot dip galvanised Gate. Using 72 X 72 X 4.8mm Sq. GI Pipe Frame with Top pipe bending in heavy duty hydraulic press with sand packing and hot bending to form double arch as per drawing profile, 20mm hot dip galvanised sq. rod for verticals at 150mm c/c, as shown in the drawing including providing hot dip galvanised forged ornamental design in between sq. rods and heads at top, middle and bottom. Intermediate supports of 75X12 mm and 50X6 mm arch bend to hot dip galvanised flats. The work is inclusive of throughing GI flat GI sq. rods, placing, welding all the joints including grinding, finishing metal putty, painting two coats enamel painting. The rate is inclusive of all materials like GI sq. pipe, GI sq. rods, GI forged designs etc., heavy duty hinges are made out of 75mm solid sq. block assembled with 20mm dia bearing in three places for each flop. Heavy Duty Locking arrangements at tow places including cost of labour, painting, erecting charges using hoist pulley cranes with all lead and lift, loading, transportation, unloading, scaffolding charges and all other incidental charges for successful completion of the work as per directions of the Engineer-in-charge of the work. (Data Rate								
		Rmt							
	For Gate								
	Shankarnag Park Yelahanka								
	West gate 1		1	3.90		2.75	10.73		
	North gate 2		1	2.50		2.25	5.63		
	Hanuman Temple Yelahanka		1	4.85		2.65	12.85		
	Nisarga Park								
	Gate-1		1	1.40		2.80	3.92		
	Gate-2		1	6.70		3.30	22.11		
	Gate-3		1	1.30		2.80	3.64		
	Gate-4		1	6.30		3.30	20.79		
	Gate-5		1	1.00		2.75	2.75		
	Vivekananda Park								
	Gate		1	3.80		1.80	6.84		
	Deo Marvel Park								
	Gate-1		1	1.30		3.20	4.16		
	Gate-2		1	4.80		3.20	15.36		
							108.77		
					Upto 125%		15.63	12599.75	196871.09
					Above 125%		93.15	12599.75	1173635.21
	Approved Amount			12599.75					
110	Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per pecifications. complete as per specifications and directions of the Engineer in charge.								
		Cum							
	Disposal OfEarthwork						842.10		
					Upto 125%		571.90	122.21	69,891.90
					Above 125%		270.20	122.21	33,021.14
	Approved Amount			122.21					
111	Providing And Fixing Ornamental M/S Flip Dust Bins As Per Approved Rate complete as per specifications and directions of the Engineer in charge.								
		Nos							

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
							0.00	18180.00	0.00
	Approved Amount			18180.00					
112	Dismantling Kerb stone by manual means and disposal of dismantled materials with all lifts and complete as per specifications. MORTH Specification No. 202 .complete as per specifications and directions of the Engineer in charge.								
		M							
	For Kerb Stone								
	Vivekananda Park								
	Eastern Side								
			1	218.00			218.00		
	Southern Side LHS								
			1	271.50			271.50		
	At Southern Side Gate								
			1	16.00			16.00		
	Western Side LHS								
			1	264.00			264.00		
	Northern Side								
			1	261.50			261.50		
	At Park Centre Path Way								
			1	240.00			240.00		
	At Gazebo								
			1	60.00			60.00		
	Around Children Play Area								
			1	58.00			58.00		
	At Entrance To Volley Ball Court								
			1	69.00			69.00		
	At Entrance To Pathway								
			1	76.60			76.60		
	At Gym Eqipuments-1								
			1	38.00			38.00		
	At Gym Eqipuments-2								
			1	19.00			19.00		
	At Main Gate Entrance								
	Tree Guards Surrounding								
			1	33.00			33.00		
	Deo Marvel Park								
	Eastern Side								
			1	82.50			82.50		
	Northern Side								
			1	92.00			92.00		
	Western Side								
			2	49.00			98.00		
	Southern Side LHS								
			1	65.00			65.00		
	Gym Surrounding								
			1	17.30			17.30		
			2	6.20			12.40		

1991.80

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
							1991.80		
					Upto 125%		1962.79	12.85	25,216.32
	Approved Amount				Above 125%		29.01	12.85	372.73
				12.85					
113	Dismantling cement concrete flooring or plain cement concrete work including removing and conveying the debris to distance upto 200m (within average thickness of 15 cms). Including cost of materials, labour , HOM complete as per specifications and directions of the Engineer in charge.								
		Sqm							
	Vivekananda Park								
	Eastern Side								
			1	108.00	2.50		270.00		
	Southern Side								
			1	134.30	2.50		335.75		
	At Southern Side Gate								
			1	4.80	2.00		9.60		
	Western Side								
			1	130.00	2.50		325.00		
	Northern Side								
			1	129.00	2.50		322.50		
	At Park Centre Path Way								
			1	120.00	2.50		300.00		
	At Entrance To Cricket Practice Ground								
			1	3.20	2.50		8.00		
	At Entrance ToYoga Stage								
			1	49.00	3.00		147.00		
	At Gazebo								
			1	47.00	2.00		94.00		
	Around Children Play Area								
			1	53.50	2.00		107.00		
	At Entrance To Volley Ball Court								
			1	30.00	3.40		102.00		
	Deo Marvel Park								
	Pathway								
	Eastern Side								
			1	42.40	2.50		106.00		
	Northern Side								
			1	47.50	2.50		118.75		
	Western Side								
			1	48.60	2.50		121.50		
	Southern Side								
			1	33.00	2.50		82.50		
	Gym Surrounding								
			1	17.30	6.20		107.26		
							2556.86	**92.07**	**235414.19**
	Approved Amount				**92.07**				

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
114	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.43cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed 2008, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications and directions of the Engineer in charge.								
		Cum							
	Vivekananda Park								
	For Shoulder Drain								
			2	5.80	0.15	0.50	0.87		
	For CC Floring								
	At Main gate Entrance								
			1	14.00	10.00	0.20	28.00		
	At Gate For Pole Concrete								
			1	4.00	0.60	0.15	0.36		
	Nisargha Park								
	Western Side								
			1	18.00	6.00	0.15	16.20		
	Southern Side								
			1	32.10	5.80	0.15	27.93		
							73.36		
					Upto 125%		**60.26**	**5704.16**	**343746.75**
					Above 125%		**13.09**	**5704.16**	**74,693.08**
	Approved Amount			**5704.16**					
115	Providing and fixing M.S. Hand railing for Balcony with 50mm dia. M.S. hollow pipe of 14 gauge, welded to 20mmx20mm M.S. square rod placed vertically, spaced at 100mm at regular intervals of 600mm. These vertical rods laterally tied to 3 horizontal rods spaced at equal interval. These assembly is fixed to concrete by using expansion bolts and welding the same to reinforcement bars and making good the surface. All the joints and sections hould be cut to length, welded and grinded wherever necessary etc., complete . The work includes cost of all materials, labour charges for all items of work, hire charges for welding, cutting and grinding equipment, and electricity charges, etc., complete as per specification and directions of the Engineer in charge.								
		Sqm							
	Vivekananda Park								
			3	5.70		1.20	20.52		
							20.52	**3040.50**	**62,391.14**
	Approved Amount			**3040.50**					
116	Providing and applying enamel metal paint two coats (exclusive primer coat) over new steel or other metal surfaces brushing to give an shade after cleaning oil grease dirt and other forien matters including cost of materials labour complate as per specifications and directions of the Engineer in charge.								
		Sqm							
							0.00	**101.71**	**0.00**
	Approved Amount			**101.71**					
117	Badminton Court Net as per the specification and directions of the Engineer in charge.								

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
		Each							
			1						
							1.00		
	Approved Amount			2020.00			1.00	2020.00	2,020.00
118	Badminton Court Net Pole as per the specification and directions of the Engineer in charge.								
		Nos							
			2						
							2.00		
	Approved Amount			10100.00			2.00	10100.00	20,200.00
119	Volley ball Court Net as per the specification and directions of the Engineer in charge.								
		Each							
			1						
							2.00		
	Approved Amount			3030.00			2.00	3030.00	6,060.00
120	Volley Ball Court Net Pole as per the specification and directions of the Engineer in charge.								
		Set							
			1						
							1.00	10100.00	10,100.00
	Approved Amount			10100.00					
121	Executive Bench-Made out of Sadarahalli grey stone with hand supports with 3 line finishing with arch design with 100mm slabs. Height 90X Length 1500 width 45 cms (Data approved rate) complete as per specifications and directions of the Engineer in charge								
		Nos							
			68						
							68.00		
	Approved Amount			18382.00			68.00	18382.00	1249976.00
122	Providing and filling sand in trenches to required depth including watring ramming with all leads and lift complete as per specifications and directions of the Engineer in charge								
		Cum							
							0.00	2205.44	0.00
	Approved Amount			2205.44					
123	. Clearing and grubbing road land including uprooting rank vegetation, grass, brush, shrubs, saplings and trees of girth upto 300mm, by manual means, in area of light jungle, removal of stumps, disposal of unserviceable materials, stacking of serviceable materials labour charges complete as per specifications and directions of the Engineer in charge								
		Sqm							
							0.00	10.71	0.00
	Approved Amount			10.71					
124	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications and directions of the Engineer in charge.5km lead= 57+2.0x1.28x5 =69.80								
		Cum							
	Vivekananda Park								
	New Drain								
	Beside Entrance Building								
			1	15.40	1.20	1.10	20.33		

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	At Entrance gate								
	For Sump		1	15.10	1.20	1.10	19.93		
	Desilt Of Drain		1	4.60	3.40	3.00	46.92		
	Eastern Side								
	Southern Side		1	108.00	1.20	0.80	103.68		
	Western Side		1	134.00	0.90	0.85	102.51		
	Northern Side		1	130.00	0.90	0.85	99.46		
	For CC Floring		1	133.00	0.60	0.75	59.85		
	At Main gate Entrance								
	Nisargha Park		1	14.00	10.00	0.30	42.00		
	Western Side								
	Southern Side		1	18.00	6.00	0.30	32.40		
	Nisargha Park		1	32.10	5.60	0.30	53.93		
	New Drain								
	Western Side		1	37.50	0.80	0.80	24.00		
	Eastern Side		1	41.00	0.80	0.80	26.24		
	For Sump		1	3.00	2.20	3.00	19.80		
	Over Burden earth		1	43.00	8.10	0.30	104.49		
	Deo Marvel Park								
	New Drain								
	Southern Side		1	6.00	1.00	1.00	6.00		
							761.53		
					Upto 125%		**657.89**	**209.68**	**137943.22**
					Above 125%		**103.64**	**209.68**	**21,730.93**
	Approved Amount			**209.68**					
125	Providing laying plain/ reinforced cement concrete for side Drains Using M20 nominal mix Concrete with OPC at 300kgs.With 20mm and Down size granite metal coarse aggregate at 0.69cum and fine aggregate at 0.43cum Machne mixed, well compacted for wall and Bottom including centering shuttering,cost of materials,HOM of Machinery,Curing Etc.,Complete								
		Cum							
	Vivekananda Park								
	New Drain								
	Raft								
	Beside Entrance Building								
			1	15.40	1.00	0.20	3.08		
	At Entrance gate								
			1	15.10	1.20	0.20	3.62		

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Wall								
	Beside Entrance Building					GF	6.70		
	At Entrance gate		2	15.40	0.20	0.80	4.93		
	Deo Marvel Park		2	15.10	0.20	0.90	5.44		
	New Drain								
	Raft								
	Southern Side								
	Wall		1	6.00	0.90	0.15	0.81		
	Southern Side								
	Toilet		2	6.00	0.15	0.60	1.08		
	Vivekananda Park								
	Plinth Beam Concrete								
			2	5.50	0.20	0.40	0.88		
	Coloumns		2	5.50	0.20	0.40	0.88		
	Roof Beam		8	0.20	0.40	2.90	1.86		
			2	5.50	0.20	0.25	0.55		
	Roof Slab		2	5.50	0.20	0.25	0.55		
			1	6.40	6.10	0.20	7.81		
							31.48		
					Upto 125%		**11.61**	**7140.90**	**82,923.72**
					Above 125%		**19.87**	**7140.90**	**141886.15**
	Approved Amount			**7140.90**					
126	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,. (Data Rate)complete as per specifications and directions of the Engineer in charge								
		Sqm							
	Nisargha Park								
	New Drain								
	Western Side								
			1	37.50	0.60		22.50		
	Eastern Side								
			1	41.00	0.60		24.60		
	Deo Marvel Park								
	New Drain								
	Southern Side								
			4	0.60	0.90		2.16		
							49.26		
					Upto 125%		**29.03**	**2360.37**	**68,509.74**
					Above 125%		**20.24**	**2360.37**	**47,762.09**
	Approved Amount			**2360.37**					
127	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specificaitons and directions of the Engineer in charge								
		Sqm							

Scanned by TapScanner

Sl No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Vivekananda Park								
	For Sump Side Wall								
			4	4.60		2.70	49.68		
			4	3.40		2.70	36.72		
	Nisargha Park								
	For Sump Side Wall								
			4	3.00		2.70	32.40		
			4	2.20		2.70	23.76		
	Toilet Area								
	Lintel		2	0.90		0.15	0.27		
	Toilet								
	Vivekananda Park								
	Footing Raft		8	6.00	0.30		14.40		
	Column upto Plinth		8	1.20	0.90		8.64		
							165.87		
					Upto 125%		**135.40**	**276.21**	**37,399.48**
					Above 125%		**30.47**	**276.21**	**8,416.26**
	Approved Amount			**276.21**					
128	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for suspended floors, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specificaitons for heights more than 3.50m from ground level. - 0 to 5 mtrs.complete as per specificaitons and directions of the Engineer in charge								
		Sqm							
	Vivekananda Park								
	For Sump Top Slab		1	4.60	3.40		15.64		
	Nisargha Park								
	For Sump Top Slab		1	3.00	2.20		6.60		
	Toilet Area								
	Slab		1	4.20	4.75		19.95		
	Toilet								
	Vivekananda Park								
	Plinth Beam Concrete		4	5.50	0.30		6.60		
			4	5.50	0.30		6.60		
	Roof Beam		4	5.50	0.28		6.16		
			4	5.50	0.28		6.16		
	Roof Slab		1	6.40	6.10		39.04		
							106.75		
					Upto 125%		**36.45**	**428.24**	**15,609.35**
					Above 125%		**70.30**	**428.24**	**30,105.27**
	Approved Amount			**428.24**					

Scanned by TapScanner